
WUF-W + SHEAR TAB BEAM TO COLUMN CONNECTIONS ACTIVITY





WUF-W + SHEAR TAB BEAM TO COLUMN CONNECTIONS ACTIVITY

ACTUAL BILL OF MATERIALS

- (1) B4001 beam
- (1) C4001 column
- (4) P4003 column web stiffeners
- (1) C4002 column
- (2) P4001 base plates
- (2) P4002 shear tab
- (4) ½ ø×1½" long bolts, nuts, and washers
- (2) 4" long ceramic backer bar
- (2) ³/₄×3" long wood quarter-round paint grey to simulate weld metal
- (4) ³/₄×4" long wood quarter-round paint grey to simulate weld metal
- (1) ¾×5" long wood quarter-round paint grey to simulate weld metal
- (2) ¾×6½" long wood quarter-round paint grey to simulate weld metal
- (2) $\frac{1}{16} \times \frac{1}{2} \times 3$ " long flexible magnetic tape
- (4) $\frac{1}{16} \times \frac{1}{2} \times 4$ " long flexible magnetic tape
- (1) $\frac{1}{16} \times \frac{1}{2} \times 5$ " long flexible magnetic tape
- (2) 1/16×1/2×61/2" long flexible magnetic tape

FABRICATION

- Fabricate all individual pieces
- Weld columns and shear tabs to base plates as shown in the shop document
- Weld (2) lower column web stiffeners as shown in the shop document only
- Weld underside of (2) top column web stiffeners only, leaving top side clear for demonstration
- Paint wood components grey, if you prefer
- Attach magnetic tape to corresponding ceramic backer bars or quarter-round pieces

ACTIVITY


- Start The two columns should be placed around 2 ft apart. Orient the beam with the beveled flanges near the column with the web stiffeners and the plain end near the column with just the shear tab.
- This activity will require two, and possibly three, pairs of hands
- Place the web stiffeners at the marked locations within the column flanges
- Add the welds to hold the stiffeners in place
- Hold up the WF beam to align the bolt holes in the beam with the bolt holes of the shear tabs
- Install and finger-tighten the bolts
- Add the ceramic backer bars below the bevels
- Add the welds in the bevels
- When the activity and the conversation are complete, undo the actions for the next participant

HIGHLIGHTS

- Note which actions occur in the shop and which occur on a job site
- Stiffeners and miscellaneous connection pieces are installed when the column is lying on its side, so this isn't exactly how a column would be fabricated in a shop
- Note that the full penetration welds are set to be performed from the top and not the bottom to make welding safer and easier
- Explain the functional difference between the fixed (can not rotate) and pinned (can rotate) connections
- Note how much more work (labor) is involved in the fixed connection compared to the pinned connection



aisc.org/IBuiltThat





DATE	NO.	DESCRIPTION	BY					
02/08/2024		SSUED FOR CONSTRUCTION (IFC04)						
02/06/2024	A	ISSUED FOR APPROVAL (IFA04)	СН					
CONTACT US IF YOU OF THESE PROBLEM * DAMAGED STEEL C* * IMPROPER FIT * FIELD MODIFICATIO * QUESTIONS ABOUT	S: ONNECTIONS INS	INDIANAPOLIS, INDIANA 317.818.1622 317.818.1255 (Fax)						
CALL OUR PROJECT		WORKFORCE ZONE ACTIVITIES						
) 818-1622 818.1622	SAN ANTONIO, TX						
ELECTRODES E70XX	UN	O CONTRACTOR AISC W/ LENEX STEEL COMPANY						
WELDS 1/4" FILLET	UN							
OPEN HOLES 13/16"Ø	UN	0						
BOLTS A325N_TC	UN	O DESCRIPTION CH 02/01/2024 NASCC 2	024					
_		ACTIVITY #4 CHECK BY KE 02/01/2024 E4	nev 0					

Tekla Structures

QTY.	SITE BOLTS	LENGTH
4	1/2"Ø A307 BOLT	1 1/2"

SEQ	QTY	
4	1	





SHOP NOTE: AISC WORKFORCE PROJECT WOULD PREFER CERAMIC BACKERS AND WANTS THEM ATTACHED TO BEAM FOR DEMONSTRATION PURPOSES. SHIP HOW LENEXFAB FEELS BEST TO ENSURE THIS WORKS


ONE - BEAM - B4001


W 7 7/8" x 3/16" F 4" x 3/16"

											02/06/2024 A ISSUED FOR APPROVAL (IFA04) DATE NO. DESCRIPTION			
g	RILL OF MATERIAL								ALL WELDING TO BE DONE IN ACCORDANCE WITH ANSI/AWS D1.1 STRUCTURAL WELDING CODE - STEEL, OF LATEST ISSUE PROJECT NAME WORKFORCE ZONE ACTIVITIES		☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐			
oture G E	y Qty a. Tot	Piece Mark	Description	Length	Weight Total	Remarks	Adv Mill #	Steel Grade		LOCATION SAN ANTONIO, TX		450 E. 96TH STREET, SUITE 100 INDIANAPOLIS, INDIANA		
Stru	1	B4001	BEAM		19				HOLES 13/16"Ø BOLTS A325N_TC UNC	CONTRACTOR		317.818.1622 317.818.1255 (Fax)	'X)	
ekla	1 1		W8X10	1'-11 1/4"	19			A992		AISC W/ LENEX STEEL COMPANY	DESCRIPTION	DRN BY CH 02/01/2024 JOB No. NASCC 2024		
	2 2	bk4001	PL1/4"X1"	0'-5"	0	CERAMIC		Misc_Un***		ARCHITECT	BEAM	CHKD BY CH 02/01/2024 DRG No. B4001		

QTY. SITE BOLTS LENGTH

SEQ	QTY
4	1





ONE - COLUMN - C4001

W 7 7/8"x3/16" F 4"x3/16"

				BILL OF	MATERIAL	-				
	Qty Ea.	Qty Tot	Piece Mark	Description	Remarks	emarks Adv		ALL WE		
s		1	C4001	COLUMN		52				WITH AN
cture	1	1		W8X10	2'-0"	20			A992	
Stru	1	1	p4001	PL1/2"X14"	1'-2"	28			A572-50	HOLES
Tekla	4	4	p4003	PL3/16"X1 3/4"	0'-7 1/2"	3			A572-50	COPES
-	1	1	p4004	PL1/2"X4"	0'-6"	1			A572-50	PAINT

				02/0			
Steel				D.			
Grade	ALL WELDING TO BE DONE IN ACCORDANC WITH ANSI/AWS D1.1 STRUCTURAL WELDIN		PROJECT NAME WORKFORCE ZONE ACTIVITIES				
	CODE - STEEL, OF LATEST ISSUE		WORKI ORGE ZONE ACTIVITIES				
A992			LOCATION				
			SAN ANTONIO, TX				
A572-50	HOLES 13/16"Ø BOLTS A325N_TC	UNO	CONTRACTOR				
A572-50	COPES 1/2" RADIUS	UNO	AISC W/ LENEX STEEL COMPANY	DESC			
	AESS CAT.	UNO	ARCHITECT				
572-50	PAINT UNP	UNO					

02/08/2024		ISSUED FOR CONSTRUCTION (IFC04)	$C \sqcup$
02/00/2024	ZŌZ	1990ED FOR CONSTRUCTION (IFC04)	СП
02/06/2024		ISSUED FOR APPROVAL (IFA04)	CH
DATE	NO.	DESCRIPTION	BY


450 | 317.8


COLUMN


LENEX STEEL CO. 450 E. 96TH STREET, SUITE 100 INDIANAPOLIS, INDIANA 317.818.1622 | 317.818.1255 (Fax)

DRN BY CH 02/01/2024 JOB No. NASCC 2024 CHKD BY CH 02/01/2024 DRG No. C4001

QTY. SITE BOLTS LENGTH







ONE - COLUMN - C4002

W 7 7/8" x 3/16" F 4" x 3/16"

			חוון סר	NAATEDIAL					1		02/06/2024 A ISSUED FOR APPROVAL (IFA04) DATE NO. DESCRIPTION		
		BILL OF MATERIAL							ALL WELDING TO BE DONE IN ACCORDANCE	PROJECT NAME	DATE NO.	DESCRIPTION	BY
υ	ty Qty a. Tot	Piece Mark	Description	Length	Weight Total	Remarks	Adv Mill #	Steel Grade	WITH ANSI/AWS D1.1 STRUCTURAL WELDING CODE - STEEL, OF LATEST ISSUE	WORKFORCE ZONE ACTIVITIES		☐ // LENEX STEEL CO.	
ture	1	C4002	COLUMN		50					LOCATION SAN ANTONIO, TX		450 E. 96TH STREET, SUITE 100 INDIANAPOLIS, INDIANA	
on_	1 1		W8X10	2'-0"	20			A992		, , , , , , , , , , , , , , , , , , ,		🗆 / 🚺 317.818.1622 317.818.1255 (Fax	ax)
Ś	' '		WOXIU	2-0	20			A99Z	HOLES 13/16"Ø BOLTS A325N_TC UNO	CONTRACTOR			
sk kla	1 1 1	p4001	PL1/2"X14"	1'-2"	28			A572-50	COPES 1/2" RADIUS UNO	AISC W/ LENEX STEEL COMPANY	DESCRIPTION	DRN BY CH 02/01/2024 JOB No. NASCC 2024	,
⊢	_	1	<u> </u>				_		AESS CAT. UNO	ARCHITECT]	CLIKD DV DDC Na	
L	1 1	p4002	PL1/2"X4"	0'-5"	3			A572-50	PAINT UNP UNO		COLUMN	CHKD BY CH 02/01/2024 DRG No. C4002	